

## BILL OF QUANTITY

NAME OF WORK: Dismantling cement concrete floor and flooring with ceramic tiles at ITI, Urkhul, Manipur.

| Sl No. | Description of items   | Qty    | Unit | Rate (in rupees) |           |
|--------|--|--------|------|------------------|-----------|
|        |  |        |      | (in figure)      | (in word) |
| 1      | 2  | 3      | 4    | 5                | 6         |
| 1      | Demolition below G.L. upto 1 m depth and disposal of unserviceable materials within 50 m lead – unreinforced cement concrete upto 15 cm thickness.   | 29.74  | cum  |                  |           |
| 2      | 1:2:4 ( 1 Cement: 2 coarse sand : 4 graded stone aggregate 40 mm nominal size)   | 20.52  | cum  |                  |           |
| 3      | Cement Mortar 1 : 4 (1 cement : 4 coarse sand)   | 11.19  | cum  |                  |           |
| 4      | Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red, Brown laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the | 212.13 | sqm  |                  |           |
| 4      | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)  | 296.00 | sqm  |                  |           |