

BILL OF QUANTITY

NAME OF WORK: Repairing and Renovation of Food Processing and Cosmetology building at ITI complex, Imphal West, Manipur. (Sh:- Ceramic Tiles Flooring)

Sl No.	Description of items	Qty	Unit	Rate (in rupees)	
				(in figure)	(in word)
1	2	3	4	5	6
1	Demolition below G.L. upto 1 m depth and disposal of unserviceable materials within 50 m lead – unreinforced cement concrete upto 15 cm thickness.	60.77	cum		
2	1:2:4 (1 Cement: 2 coarse sand : 4 graded stone aggregate 40 mm nominal size)	24.31	cum		
3	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red, Brown laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	243.10	sqm		
4	Tile work in skirting, risers of steps and dado (upto 2 m height) over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm including pointing in white cement mixed with pigment of matching shade complete. 8 mm thick.	15.32	sqm		