

BILL OF QUANTITY

NAME OF WORK: Dismantling cement concrete floor and flooring with ceramic tiles at ITI, Kakching, Manipur.

Sl No.	Description of items	Qty	Unit	Rate (in rupees)	
				(in figure)	(in words)
1	2	3	4	5	6
1	Demolition below G.L. upto 1 m depth and disposal of unserviceable materials within 50 m lead – unreinforced cement concrete upto 15 cm thickness.	18.00	cum		
2	1:2:4 (1 Cement: 2 coarse sand : 4 graded stone aggregate 40 mm nominal size)	24.30	cum		
3	Cement Mortar 1 : 4 (1 cement : 4 coarse sand)	9.45	cum		
4	Providing and laying Ceramic glazed floor tiles 300x300 mm(thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red, Brown laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand) including pointing the joints with white	189.00	sqm		
5	Renewing glass panes, with putty and nails wherever necessary:				
	Renewing glass panes and refixing existing wooden fillets:				
	Float glass panes of thickness 4 mm	19.80	Sqm		