

BILL OF QUANTITY

Name of Work : Providing and fabrication of steel rack for store room at Industrial Training Institute (ITI), Takyel, Imphal West.

Sl No.	Description of items	Qty	Unit	Rate (in rupees)	
				(in figure)	(in word)
1	2	3	4	5	6
SH: STEEL WORK					
1	Steel work welded in built up section/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using steel etc. as required.				
	In grating, frames, guard bar, railing, brackets, gates and similar works.	4294.78	kg		
2	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.				
	Using flats 30x6mm for diagonal braces and central cross piece	9.00	sqm		
SH: FINISHING					
3	Applying priming coat:- With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel work (second coat)	163.90	sqm		
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture.	163.90			